# RCD TEST BUTTONS AND THE FUNCTIONAL TESTS

## WHAT DOES THE CLIENT ACTUALLY CARE ABOUT?

Press each RCD's test button once more after the timed tests, to show it's still working.

Then **functional testing**: put the lamps in, energise, and prove everything does what it's for.

- Every light switch, every two-way and intermediate, works the lights it should.
- The cooker switch, its neon, the oven fires up.
- Isolators and switching devices isolate and switch.
- RCDs, AFDDs and SPDs show they're in service.

> **To the client, this is the test that matters.**
> They paid for it to work. Your continuity tests already showed the switches make and break — this is where you prove it with the power on.

Free section from Sparky Study Notes. The full Level 3 notes, 1,463 practice questions and the video lessons: sparkystudynotes.co.uk